No.	Items of work	Unit	Quantity	Rate
				Rs. a. p.
6	Constructing man-hole 3′ dia. inside as per design complete including providing and fixing 21″ dia. C.I. man-hole cover and frame up to 3′ height	Each	2	
7	Do 4′ dia. and as above with necessary C.I. steps 3′ to 4′ height	,,	2	
8	Do 4′ to 5′ depth as above	,,	2	
9	Do 5′ to 6′ deep as above	,,	3	
10	Do 7′ to 8′ deep as above	,,	1	
11	Repairing road crossing with fresh jelly consolidating, etc.	R.ft.	18	
12	Encasing 6″ pipe line with cement concrete alround ..	,,	20	
13	Dismantling concrete benches existing man-hole and redoing	Each	1	

K. S. HUTCHA RAO,
Sanitary Engineer.

KOLAR DIVISION.

Notification dated 28th November 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 22nd December 1939, for improving the Feeder Channel to Devar Mallur, Major Tank, Register No. 32, Sidlaghatta Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for Improving the Feeder Channel to Devar Mallur Major Tank." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury challan for earnest money of Rs. 140, paid to the treasury to the credit of "17(*a*) P. W. Deposits," against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 22nd December 1939 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the Division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of June 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.

(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.

(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.

(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.

(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tenders in the prescribed form are obtainable from the Office of the Executive Engineer, Kolar Division, Kolar, only on a payment of four annas per form

Abstract estimate for improving the Feeder Channel to Devar Mallur, Major Tank, Register No. 32, Sidlaghatta Taluk.

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
	I. Channel.		Rs. a. p.		
1	Cutting and removing jungle with roots ..	Fur.	6 0 0	8	
2	Earthwork excavating channel in chattu and ordinary soil mixed	C.yd.	0 4 0	2,905	
3	Earthwork to embankment and forming with consolidation	,,	0 4 0	2,459	
4	Excavating foundation in breach chattu soil	,,	0 4 0	110	
5	Constructing new burnt stone revetment with jelly backing	,,	1 8 0	118	
6	Deviating halla water and putting embankment, etc.	L. S.	..	..	
7	Providing zero and mile stones including painting, etc., complete	No.	7 8 0	2	
8	Providing ½ furlong stones	,,	2 4 0	19	
	Total ..	..	..	..	
	II. Constructing Releiving Weir (65 ft.)				
1	Earthwork excavating foundation for body wall and apron	C.yd.	0 3 0	90	
2	Filling stone jelly concrete in surki mortar for foundation	C.ft.	0 4 0	188	
3	Burnt brick in surki mortar for body wall and returns	,,	0 4 6	225	
4	Providing burnt stone slabs 6″ thick dressed and fixed	S.ft.	0 5 0	266	
5	Plastering with surki mortar	Sqr.	3 8 0	3.40	
6	Constructing new burnt stone apron ..	C.yd.	1 8 0	64	
7	Providing joggle joints to slabs over body wall	Each	0 12 0	10	
8	Draft clearing and diverting water ..	L. S.	..	..	
	Total ..	..	..	..	
	III. Constructing Drop of 4 ft.				
1	Earthwork excavation, foundation of body wall and apron	C.yds.	0 3 0	15	
2	Stone jelly concrete in surki mortar for body wall	C.ft.	0 4 0	54	
3	Burnt brick in surki mortar for body wall and return	,,	0 4 6	216	
4	Providing burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	0 5 0	49	
5	Plastering with surki mortar	Sqr.	3 8 0	1.35	
6	Providing burnt stone apron with jelly backing, etc., complete	C.yd.	1 8 0	9	
	Total ..	..	..	..	

N.B.—Another drop similar to the above to be constructed as included in the sanctioned estimate.

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
			Rs. a. p.		
	IV. Constructing Drop of 3 feet.				
1	Earthwork excavation for foundation of body wall and apron	C.yd.	0 3 0	13	
2	Stone jelly concrete in surki mortar for body wall	C.ft.	0 4 0	54	
3	Burnt brick in surki mortar for body wall and returns	,,	0 4 6	169	
4	Providing burnt stone slabs 6" thick dressed and fixed in mortar	S.ft.	0 5 0	49	
5	Plastering with surki mortar	Sqr.	3 8 0	1.17	
6	Providing burnt stone apron new with jelly backing, etc., complete	C.yd.	1 8 0	9	
	Total ..	..	..	..	

Notification dated 2nd December 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 22nd December 1939, for restoring Korenahalli Malladapalli Tank, Reg. No. 250 in Srinivasapur Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for restoring Korenahalli, Mallenahalli Tank, Reg. No. 250 in Srinivasapur Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by treasury chellan for the earnest money for Rs. 750 paid to the treasury to the credit of "17 (*a*) P. W. Deposits" against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 22nd December 1939 at Kolar. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications. A reserve of 5 per cent will be held in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in schedule of quantities, the contractor will be paid at either his tendered rate for each item on the prevailing schedule of rates in the Division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per

cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1941, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress, of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N. B.—Copies of tenders in the prescribed form are obtainable from the office of the Executive Engineer, Kolar Division, Kolar, only on a payment of Re. 0–4–0 per form.

Amount of estimate Rs. 15,000.

Abstract estimate for restoring Korenahally Malladapally Tank of Srinivasapur Taluk, Register No. 250.

Item No.	Description of work	Per	Rate	Quantity	Rate to be offered
	Bund at R. L. 55.00 (*Top width* 6').		Rs. a. p.		
1	Earthwork to bund with watering and tamping with lead and lift, etc., complete	C.yd.	0 4 0	21,920	
2	Turfing	S.yds.	0 0 9 (as per schedule)	13,746	
3	Clay puddle wall mixed with gravel	C.yds.	0 8 0	82	
4	Gravel backing with lead	„	0 6 0	743	
5	New stone revetment with jelly backing and wedging	„	1 8 0	2,975	

Item No.	Description of work	Per	Rate	Quantity	Rate to be offered
			Rs. a. p.		
6	Grade stones with figuring and painting, etc., complete	No.	1 4 0	50	
7	Index stones do	„	0 6 0	50	
8	Register No. and date stone cutting figures and painting	„	3 0 0	1	
9	B. M. Stones	„	2 8 0	2	
10	Gauge stones do	„	15 0 0	1	
11	Jungle clearing, removing ant-hills and filling sand and cutting grips, etc.	Grade	5 0 0	50	
	Weir at 50.00.				
1	Earthwork excavation and using the same to bund	C.yds.	0 3 6	529	
2	Stone jelly concrete in surki mortar	C.ft.	0 4 0	1,395	
3	Burnt brick in surki mortar	„	0 4 0	3,561	
4	Nice surki mortar plastering	Sqrs.	3 8 0	8.63	
5	Burnt stone slabs 6″ thick dressed	S.ft.	0 4 6	1,400	
6	Rough stone apron with jelly backing and wedging	C.yds.	1 8 0	322	
7	Joggle joints	Each	1 0 0	42	
	Sluice No. 1 *at* 44.00.				
1	Earthwork cutting bund	C.yds.	0 3 0	28	
2	Refilling with watering and tamping	„	0 2 0	31	
3	Stone jelly concrete in surki mortar	C.ft.	0 4 0	341	
4	Burnt brick in surki mortar	„	0 4 0	267	
5	Burnt stone slabs 6″ thick dressed	S.ft.	0 4 6	257	
6	Plastering with surki mortar and rendering with cement	Sqr.	6 0 0	4·01	
7	Cutting orifice in slabs	Each	1 0 0	4	
	Sluice No. 2 *as per sluice No.* 1.				
1	Earthwork cutting bund	C.yds.	0 3 0	28	
2	Refilling with watering and tamping	C.yd.	0 2 0	31	
3	Stone jelly concrete in surki mortar	C.ft.	0 4 0	341	
4	Burnt brick in surki mortar	„	0 4 0	267	
5	Burnt stone slabs 6″ thick dressed	S.ft.	0 4 6	257	
6	Plastering with surki mortar and rendering with cement	Sqr.	6 0 0	4.01	
7	Cutting orifice in slabs	S.yd.	1 0 0	4	

C. R. IYENGAR,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 18th November 1939.

CONSTRUCTING A GIRDER BRIDGE WITH 12′ ROAD WIDTH ACROSS THE RIVER DANDAVATI IN SORAB TALUK (5/6 OF SORAB-ANAVATTI ROAD).

The attention of the public is hereby invited to the advertisement in pages 2356-2358, Part VI of the *Mysore Gazette*, dated 23rd November 1939, calling for tenders for constructing a girder bridge with 12′ road width across the River Dandavati in Sorab Taluk (5/6 of Sorab-Anavatti Road).

Each tender must be accompanied by a Treasury challan for having deposited Rs. 1,500 as earnest money.

The last date for receiving tenders is 11th December 1939 up to 4 P.M.